

MATERIAL SCHEDULE.

DESCRIPTION	No. REQD	LENGTH/SIZE
1. FLOAT: CONCRETE FLOTATION UNIT. FOR CONSTRUCTION DETAILS SEE DRG. WWF1-BASE	1	11m x 2.46m x 0.61m Deep
2. STEELWORK: FOR DETAILS OF STEELWORK FRAME SEE DRG. WWF1-FAB		
3. TIMBER: (a) FENDER TO BE YELLOW BALAU OR SIMILAR APPROVED.	2	0.095 x 0.045m x 11m
(b) DECKING BOARDS TO BE YELLOW BALAU OR SIMILAR APPROVED.	77	0.145 x 0.022m x 2m
4. DUCT COVER: "WALCON" EXTRUSION NO. 6C.	4	11.46m
5. FIXINGS & FITTINGS: FULL BREAKDOWN OF FIXINGS & FITTINGS DETAILED ON SCHEDULE SUPPLIED WITH THIS ITEM.		
6. CONNECTIONS: STANDARD CONNECTION DETAILS ARE SHOWN ON SYSTEM 21 E/E STANDARD DRAWING		

7. SHIPPING SCHEDULE:

ITEM	UNPACKED VOL.	UNPACKED WT.
STEEL FRAME	5.1m ³	858kg
DECKED FRAME	5.9m ³	1749kg
FLOTATION UNIT	16.5m ³	8123kg

B	MD	31.03.00	FAME UPDATE
A	ESM	6.93	THROUGH BOLT CHANGED TO M24
Rev.	By	Date	Description

Client
WORKING HARBOURS

Title
**DECKED WALIFLOTE
LAYOUT & DEALS FOR
11.5m x 2.6m WIDE WALKWAY**

Drawn	Checked	Date	Scale
ESM		19.03.92	1:50



Segensworth West, Fareham, Hampshire PO15 5SR
Telephone: +44 (0) 1489 579977
Facsimile: +44 (0) 1489 579988

C.A.D. Path	A3
Drawing No. WWF1-GA	REV. B

