



MATERIAL SCHEDULE.

DESCRIPTION	No. REQD	LENGTH/SIZE
STEELWORK: 1. FOR DETAILS OF STEELWORK FRAME SEE DRG. M2000/008		
2. TIMBER: (a) FENDER TO BE YELLOW BALAU OR SIMILAR APPROVED. (b) DECKING BOARDS TO BE YELLOW BALAU OR SIMILAR APPROVED.	2 @ 7.5 77 @ 1.37 2 @ 7.5	15m 185.0 m
(c) SPINE MEMBERS TO BE WALCON EXTRUSION No 5 TIMBER SECTIONS SEE DRG M673/4	3 @ 7.5	22.5 m
3. DUCT COVER: WALCON EXTRUSION NO. 6C.	6 @ 2.3	15.0 m
4. FLOATS: CONCRETE FLOATATION UNITS. FOR STANDARD DETAILS SEE DRG. M673/3.	2	1.83 x 1.53 x 0.686 Deep
5. FIXINGS: FULL BREAKDOWN OF FIXINGS DETAILED ON COMPONENT LIST SUPPLIED WITH THIS DRAWING.	SEE COMP. LIST	
6. CONNECTIONS: STANDARD CONNECTION DETAILS ARE SHOWN ON DRG. M210/100		

7. SHIPPING SCHEDULE:

ITEM	UNPACKED VOL.	UNPACKED WT.
STEEL FRAME	2.43 m ³	510 kg
DECKED FRAME	2.88 m ³	874 kg
FLOTATION UNITS	4.16 m ³	960 kg

A	MD	15.05.01	FRAME UPDATE
Rev.	By	Date	Description

Client **SYSTEM 21 WW4**

Title **7.5m x 2m WALKWAY GENERAL ARRANGEMENT**

Drawn **ESM** Checked **ESM** Date **09.10.92** Scale



Segensworth West, Fareham, Hampshire PO15 5SR
Telephone: +44 (0) 1489 579977
Facsimile: +44 (0) 1489 579988

C.A.D. Path **A3**
Drawing No. **S21/WW4 - ga** REV. **A**