

Godfrey Alner
Property, Business and Regulatory
Hampshire County Council
Three Minsters House
76 High Street
WINCHESTER,
SO23 8UL



Tel: 01489 574000
Fax: 01489 574014
E-Mail: keith.whiting@keison.ltd.uk

QUOTATION

Date: 16 September 2010

Quote No: 3964

Dear Godfrey,

RE: Locks Heath Childrens and Youth Centre – Kitchen Refurbishment
(Revised to include new Integral Dishwasher and Washing Machine and Stainless Steel Cooker)

With reference to your recent request I have the pleasure in providing you with this quotation and confirming the following details.

- Employ Electrical contractor to isolate and remove supply to existing electric cooker.
- Isolate water services and carefully remove all existing cabinets and worktops and dispose of but retaining existing water heater.
- Isolate existing radiator under and form timber studwork wall to suit height of new counter top.
- Construct new timber lining and fit half height ply flush door 900mm high to kitchen entrance, door to be fitted with latch and turnback SAA lever furniture.
- Supply and fit range of kitchen units from the Magnet Edmunton range of units consisting of the following. 1, 1000mm base, 2, 1000mm sink base, 1, 800mm base, 4, 600mm base, 1 600 FF housing, 1, 800mm wall, 1, 1000mm wall, 2, 600mm wall, worktops, plinths and 900mm breakfast top.
- Supply and install integral 50/50 fridge freezer, inset stainless steel sink top, stainless steel hand wash bowl inset to top and stand alone extractor unit with charcoal filter.
- Supply and install new Hotpoint integral dishwasher to include matching door/drawer front, electrical supplies, water and waste services.
- Supply and fit wall tiling 3 courses high to perimeter of all new worktops using standard white tiles.
- Employ registered Gas installer to run a new gas supply to feed the new gas cooker.
- Supply and install new Indesit 210 SXG Stainless Steel 60cm wide free standing gas cooker including connection and commissioning using registered Gas installer.
- Prepare floor area and lay new Gerflor Tarasafe Ultra safety flooring to kitchen area flat laid and sealed at plinth abutments.
- Supply and install new Stainless steel colour front loading free standing washing machine to include new electrical supplies, and connection to waste and water services.
- Decorate new timber studwork and new joinery to match existing colours.

All for the sum of:

£9352.56

Options.

It is recommended that a thermostatic mixing valve (TMV) is fitted to the hot water supply feeding the handwash basin, however we would advise that the existing water heater will not provide adequate pressure for a TMV to operate satisfactorily, therefore we have provided a price to change the water heater for a new un-vented heater and TMV as an optional price below.

- Supply and fit new un-vented 7Ltr 2Kw water heater to include all required ancillaries to supply hand wash basin fitted inside new kitchen cabinet.
- Supply, fit and commission new Reliance heatguard TMV to include all testing and commissioning.
- Employ Electrical contractor to provide and connect supply to new heater.

All for the sum of:

£675.00

Cont'd

NOTE: We have allowed for these works to be carried out during normal working hours (Monday-Friday 08:00-17:00).

I hope that I have understood your requirements correctly, but if however you have any queries please do not hesitate to contact me further.

Yours sincerely

KEITH WHITING

Please note that all quoted prices are exclusive of VAT.