

- NOTES:
- ALL DIMENSIONS SUBJECT TO MODIFICATION ON COMPLETION OF DETAILED DESIGNS
 - ALL CIVIL WORKS TO BE CARRIED OUT BY CUSTOMER, FOUNDATION LOADINGS ON REQUEST FROM KIVERCO.
 - RECOMMENDED MAGNET LOCATION IS AFTER THE PICKING STATION. OTHER POSITIONS WILL POTENTIALLY CAUSE JAMMING POINTS. IF MAGNET MUST BE FITTED OTHER THAN ABOVE THEN CORRECT PRE-SORTING OF MATERIAL IS ESSENTIAL.

