


NOTES

1. ALL DIMENSIONS ARE IN MILLIMETRES.
2. THE REINSTATEMENT OF THE FOOTWAY STRUCTURE SHALL BE CARRIED OUT AS SOON AS PRACTICABLE AFTER BACKFILLING HAS BEEN COMPLETED.
3. WHERE TRENCH IS LESS THAN 450 WIDE, REINSTATEMENT ABOVE PIPE SHALL BE FOAMED CONCRETE TO CL.1043, OR WHERE QUANTITIES MAKE FOAMED CONCRETE IMPRACTICAL, LOWER STRENGTH CONCRETE 1 TO CL.1030.
4. WHERE LOWER STRENGTH CONCRETE 1 IS USED, TRANSVERS CRACKS SHALL BE INDUCED AT 3m CENTRES.
5. CBGM TO CL. 821 OR CL. 822 SHALL BE C5/6 WITH REFERENCE TO BS 9227.
6. TREATMENT OF LAYERS AND VERTICAL JOINTS SHALL BE IN ACCORDANCE WITH CL. 903.
7. EXISTING BLOCK OR FLAG PAVING SHALL BE CAREFULLY REINSTATED TO A MINIMUM OF 300 EITHER SIDE OF THE TRENCH EDGE AND BEDDED AS DESCRIBED IN DRAWING No. HCC11/C/045.



B	COPYRIGHT AMENDED AND NEW DIRECTORATE DETAILED	09.02.2023	AM	KM	
A	SUBBASE TO CL. 804R DELETED, CL. 803 TYPE 1F, CL. 821 AND CL. 822 ADDED, NOTES ADDED AND AMENDED AND BRANDING UPDATED	22.06.2022	CLT	KM	MC
REV	AMENDMENTS	DATE	CAD	CHKD	APPD

CONSULTANT




TIM LAWTON BEng CEng FICE FCIHT : ASSISTANT DIRECTOR OF UNIVERSAL SERVICES

SCHEME

STANDARD DETAILS

DRAWING TITLE

REINSTATEMENT OF DRAIN AND DUCT TRENCHES IN EXISTING FOOTWAYS

DESIGNER	CHECKED	SCALE @ A3
MC	JPR JPR	N.T.S
CAD	APPROVED	DATE
MC	CDP CDP	March 2020
DRAWING NUMBER	REV	
HCC11/C/095	B	

Copyright Hampshire County Council.

All rights, including translation, reserved. No part of this publication may be reproduced, stored in a retrieval system, or transmitted in any form or by any means (electronic, mechanical, photocopied, recorded or otherwise) without the prior written permission of Hampshire County Council. Requests should be directed to Hampshire Engineering Services.