



PLAN

NOTES:

1. ALL DIMENSIONS ARE IN MILLIMETRES.
2. ALL BAGWORK SHALL BE AS CLAUSE 519. ONLY HESSIAN BAGS SHALL BE PERMITTED.
3. ALL CEMENT USED IN CONCRETE SHALL BE CII(A OR B)-S OR CIII A OR B TO BS 8500-2, TABLE 1 AND ANNEX A.
4. ADDITIONAL LAYER OF BAGWORK TO BE INSTALLED BELOW INVERT BAGWORK. THE BAGS SHALL BE PINNED ENSURING THAT THE PINS DO NOT PASS THROUGH THE LOWER LAYER OF BAGWORK.
5. BEFORE ANY EXCAVATION OR PINNING OF BAGS IS UNDERTAKEN THE CONTRACTOR SHALL SURVEY THE AREA TO ENSURE THAT THERE ARE NO BURIED SERVICES BENEATH.
6. INVERT OF INCOMING PIPE SHALL BE AS SPECIFIED ON THE HEADWALL SCHEDULE OR ON THE LAYOUT DRAWINGS.

REV	AMENDMENTS	DATE	CAD	CHKD	APPD

CONSULTANT

STUART JARVIS BSc DipTP FCIHT MRTPI: DIRECTOR OF ECONOMY, TRANSPORT & ENVIRONMENT

SCHEME

STANDARD DETAILS

DRAWING TITLE

**HEADWALL TYPE 3
CONCRETE BAGWORK**

HCC CADplot: 24.Mar.2020 at 9:00am					
DRAWN	RB	CHECKED	JPR	SCALE @ A3	N.T.S
CAD	RB	APPROVED	CDP	DATE	March 2020
DRG No.	HCC11/D/095				REVISION

Copyright Hampshire County Council. 2019

All rights, including translation, reserved. No part of this publication may be reproduced, stored in a retrieval system, or transmitted in any form or by any means (electronic, mechanical, photocopied, recorded or otherwise) without the prior written permission of Hampshire County Council. Requests should be directed to the Economy, Transport & Environment Department.

Use only for Hampshire County Council Standard Details (Scheme) as indicated. Do not use for other projects without the permission of the Engineering Department.