



NOTES:

1. ALL DIMENSIONS ARE IN MILLIMETRES.
2. ALL BAGWORK SHALL BE AS CLAUSE 519.
3. ALL CEMENT USED IN CONCRETE SHALL BE CII(A OR B)-S OR CIII A OR B TO BS 8500-2, TABLE 1 AND ANNEX A.
4. ADDITIONAL LAYER OF BAGWORK TO BE INSTALLED BELOW INVERT BAGWORK. THE BAGS SHALL BE PINNED ENSURING THAT THE PINS DO NOT PASS THROUGH THE LOWER LAYER OF BAGWORK.
5. BEFORE ANY EXCAVATION OR PINNING OF BAGS IS UNDERTAKEN THE CONTRACTOR SHALL SURVEY THE AREA TO ENSURE THAT THERE ARE NO BURIED SERVICES BENEATH.

REV	AMENDMENTS	DATE	CAD	CHKD	APPD
-	-	-	-	-	-

CONSULTANT

Hampshire County Council **Engineering CONSULTANCY**

STUART JARVIS BSc DipTP FCIHT MRTPI: DIRECTOR OF ECONOMY, TRANSPORT & ENVIRONMENT

SCHEME

STANDARD DETAILS

DRAWING TITLE

**HEADWALL TYPE 3
CONCRETE BAGWORK**

HCC CADplot: 18.Sep.2015 at 2:10pm		
DRAWN	CHECKED	SCALE @ A3
RB	WW, WW	N.T.S
CAD	APPROVED	DATE
RB	CP	July 2015
DRG No.	REVISION	
HCC10/D/100	-	

Copyright Hampshire County Council. 2015

All rights, including translation, reserved. No part of this publication may be reproduced, stored in a retrieval system, or transmitted in any form or by any means (electronic, mechanical, photocopied, recorded or otherwise) without the prior written permission of Hampshire County Council. Requests should be directed to the Economy, Transport & Environment Department.