


**NOTES**

1. ALL DIMENSIONS ARE IN MILLIMETRES.
2. ALL BAGWORK SHALL BE AS CLAUSE 519. ONLY HESSIAN BAGS SHALL BE PERMITTED.
3. ALL CEMENT USED IN CONCRETE SHALL BE CII(A OR B)-S OR CIII A OR B TO BS 8500-2, TABLE 1 AND ANNEX A.
4. ADDITIONAL LAYER OF BAGWORK TO BE INSTALLED BELOW INVERT BAGWORK. THE BAGS SHALL BE PINNED ENSURING THAT THE PINS DO NOT PASS THROUGH THE LOWER LAYER OF BAGWORK.
5. BEFORE ANY EXCAVATION OR PINNING OF BAGS IS UNDERTAKEN THE CONTRACTOR SHALL SURVEY THE AREA TO ENSURE THAT THERE ARE NO BURIED SERVICES BENEATH.
6. INVERT OF INCOMING PIPE SHALL BE AS SPECIFIED ON THE HEADWALL SCHEDULE OR ON THE LAYOUT DRAWINGS.



B	COPYRIGHT AMENDED AND NEW DIRECTORATE DETAILED.	09.02.2023	AM	KM	MC
A	BRANDING UPDATED.	14.07.2022	CLT	KM	MC
REV	AMENDMENTS	DATE	CAD	CHKD	APPD

CONSULTANT

**Hampshire County Council**

**Hampshire Engineering Services**

TIM LAWTON BEng CEng FICE FCIHT : ASSISTANT DIRECTOR OF UNIVERSAL SERVICES

SCHEME

**STANDARD DETAILS**

DRAWING TITLE

**HEADWALL TYPE 5  
CONCRETE BAGWORK**

DESIGNER	CHECKED	SCALE @ A3
RB	JPR   JPR	N.T.S
CAD	APPROVED	DATE
RB	CDP   CDP	March 2020
DRAWING NUMBER	REV	
HCC11/D/105	B	

Copyright Hampshire County Council.

All rights, including translation, reserved. No part of this publication may be reproduced, stored in a retrieval system, or transmitted in any form or by any means (electronic, mechanical, photocopied, recorded or otherwise) without the prior written permission of Hampshire County Council. Requests should be directed to Hampshire Engineering Services.