


PLAN OF EXCAVATED FOUNDATION

NOTES FOR COLUMN ERECTION IN PAVED AREAS

- A. COLUMN HOLE TO BE EXCAVATED BY HAND; MANUFACTURERS DETAIL DRAWING & REQUIRED DIMENSIONS TO BE CHECKED; ASSUME "POOR" SOIL CONDITIONS
- B. HOLE TO BE CUT SQUARE AT THE BOTTOM
- C. ALL SURPLUS MATERIAL TO BE REMOVED AND DISPOSED TO TIP OFF SITE
- D. THE STEPPED HOLE METHOD OF EXCAVATION IS NOT PERMITTED
- E. REFER TO COLUMN MANUFACTURER'S GUIDANCE FOR HANDLING AND TRANSPORTATION TO PREVENT DAMAGE
- F. THE COLUMN DOOR TO FACE DOWNSTREAM FROM TRAFFIC FLOW
- G. COLUMN TO BE TRULY VERTICAL AFTER INSTALLATION
- H. INSERT CABLE ACCESS DUCT INTO COLUMN CABLE SLOT. CABLE DUCT TO BE FLEXIBLE POLYPROPYLENE - BLACK FOR DNO, IDNO SUPPLY OR ORANGE FOR PRIVATE CABLE SYSTEMS (DUCT TO BE 50MM INTERNAL DIAMETER, SMOOTH BORE)
- I. LANTERN SHALL BE INSTALLED AT 90° TO ADJACENT KERB WITH A MAXIMUM 5° UPWARD TILT (UNLESS OTHERWISE STATED ON THE STREET LIGHTING LAYOUT DRAWINGS)

NOTES

1. ALL DIMENSIONS ARE IN MILLIMETRES.
2. FOR DETAILS OF COLUMN LOCATIONS SEE STREET LIGHTING LAYOUT DRAWINGS.
3. COLUMNS SHALL COMPLY WITH BS EN 40, PD6547:2009 AND DEPARTMENTAL STANDARD BD 94/17 IN ADDITION TO THE HCC COLUMN SPECIFICATION; DESIGNERS TO VERIFY THAT COLUMN PROPOSED IS SUITABLE FOR ANY PROPOSED ATTACHMENTS; DATA SHEETS TO BE PROVIDED.
4. DURING INSTALLATION OF COLUMNS CARE IS TO BE TAKEN TO ENSURE THAT THE CORROSION PROTECTION SYSTEM OF THE LIGHTING COLUMN IS NOT DAMAGED; ALL BACKFILLING MATERIAL SHALL BE PLACED IN 150MM THICK LAYERS AND BE WELL-COMPACTED.
5. ANY DAMAGE TO THE EQUIPMENT DURING INSTALLATION (OR BEFORE ACCRUAL ONTO HCC'S INVENTORY) MUST BE REPAIRED TO A SATISFACTORY STANDARD IN ACCORDANCE WITH THE GUIDELINES GIVEN BY THAT SPECIFIC MANUFACTURER.
6. ALL DUCTING AND CABLING SHALL BE INSTALLED IN ACCORDANCE WITH THE CURRENT EDITION OF NJUG IN CONJUNCTION WITH CURRENT HAUC (UK) GUIDANCE.
7. GROUND-LEVEL / PLANTING DEPTH MARKER TAPE TO REMAIN AFFIXED TO THE COLUMN AFTER INSTALLATION TO DEMONSTRATE THE CORRECT PLANTING DEPTH HAS BEEN ACHIEVED.
8. COLUMN MANUFACTURER'S DETAIL DRAWINGS & REQUIRED FOUNDATION DIMENSIONS MUST BE CROSS-CHECKED TO ENSURE REQUIREMENTS ARE MET FOR ALL SITES.



B	COPYRIGHT AMENDED AND NEW DIRECTORATE DETAILED.	06.02.2023	AM	JH	JH
A	BRANDING UPDATED.	14.07.2022	CLT	IH	JH
REV	AMENDMENTS	DATE	CAD	CHKD	APPD

CONSULTANT

TIM LAWTON BEng CEng FICE FCIHT : ASSISTANT DIRECTOR OF UNIVERSAL SERVICES

SCHEME

STANDARD DETAILS

DRAWING TITLE

PLANTED COLUMN ERECTION DETAILS FOR LOCATIONS IN PAVED AREAS

DESIGNER	CHECKED	SCALE @ A3
WW	IH IH	N.T.S
CAD	APPROVED	DATE
WW	JH JH	March 2020
DRAWING NUMBER	REV	
HCC11/I/035	B	

Copyright Hampshire County Council.

All rights, including translation, reserved. No part of this publication may be reproduced, stored in a retrieval system, or transmitted in any form or by any means (electronic, mechanical, photocopied, recorded or otherwise) without the prior written permission of Hampshire County Council. Requests should be directed to Hampshire Engineering Services.