



NOTES

- DO NOT SCALE FROM THIS DRAWING
- ALL DIMENSIONS IN METRES UNLESS OTHERWISE STATED
- THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT DETAILS, DRAWINGS AND SPECIFICATIONS AS SPECIFIED IN THE CONTRACT DOCUMENTS.
- ANY DISCREPANCIES SHOULD BE REPORTED TO THE OVERSEEING ORGANISATION IMMEDIATELY, TO CLARIFY BEFORE STARTING WORK.
- IT IS THE CONTRACTOR'S/SUBCONTRACTOR'S RESPONSIBILITY TO ENSURE COMPLIANCE WITH THE CURRENT CODES OF PRACTICE, STANDARDS AND PRODUCT MANUFACTURES DETAILS AND SPECIFICATION.
- THE CONTRACTOR IS TO KEEP A RECORD OF ANY VARIATIONS AGREED DURING THE DURATION OF THE WORKS, INCLUDING THE RELOCATION OF SEWERS OR DRAINS, SO THAT AN "AS-CONSTRUCTED" DRAWING CAN BE PREPARED UPON COMPLETION OF THE PROJECT.
- PARTS OF THIS DRAWING SHOULD BE SHOWN IN COLOUR. IF THIS NOTE IS NOT RED REPRINT A COLOURED COPY.**
- FOR LOCATION PLAN AND SHEET LAYOUT INDEX REFER TO DRAWING NUMBER TED240601-HEH-GEN-12319908-DR-CH-0002.
- ALL HCC STANDARD DETAILS, REFERRED TO ON THIS DRAWING, ARE TO THE CURRENT REVISION AT THE DATE OF ISSUE UNLESS OTHERWISE STATED.
- ALL EXCAVATIONS TO BOUND SURFACES MUST BE UNDERTAKEN TO CLAUSE 706.3.
- ALL EXCAVATION WORKS WITHIN THE TREE PROTECTION ZONE (TPZ) TO BE CARRIED OUT BY HAND ONLY. NO MECHANICAL EXCAVATION PERMITTED. WORKS TO BE UNDERTAKEN IN ACCORDANCE WITH ARBORICULTURAL GUIDANCE AND UNDER APPROPRIATE SUPERVISION.
- TOPSOIL SUPPLY TO BE IN ACCORDANCE WITH BS 3882:2015.
- PRIOR TO THE DELIVERY AND INSTALLATION OF TOPSOIL, THE CONTRACTOR SHALL GIVE NOTICE TO THE OVERSEEING ORGANISATION AND OBTAIN WRITTEN INSTRUCTION. TOPSOIL SHALL BE DELIVERED DIRECTLY TO SITE ON THE DAY IT IS SCHEDULED TO BE SPREAD, UNLESS OTHERWISE AGREED. ALL HANDLING, STORAGE, AND SPREADING OF TOPSOIL SHALL COMPLY WITH THE REQUIREMENTS OF CLAUSE 618 OF THE SPECIFICATION FOR HIGHWAY WORKS.
- TOPSOIL HANDLING, SPREADING AND STORAGE WILL BE IN ACCORDANCE WITH BS 3882:2015. DO NOT SPREAD TOPSOIL WHEN GROUND IS FROZEN OR WATERLOGGED.
- SEED MIX WILL BE IN ACCORDANCE WITH CL 3005 OF SHW OR APPROVED EQUIVALENT. TOPSOIL TO CL618 OF SHW. SAMPLE TO BE PROVIDED FOR APPROVAL PRIOR TO INSTALLATION.

KEY

- PROPOSED TYPE 1 LAND DRAINAGE DITCH/SWALE TO STANDARD DETAIL HCC11/D/115
- PROPOSED EARTHWORKS
- PROPOSED CELLULAR CONCRETE BLOCKS
- PROPOSED TOPSOILING AND SEED
- PROPOSED CONCRETE LINED DITCH
- REINSTATED AS-DUG MATERIAL (TURF)
- PROPOSED GROUND LEVEL
- REINSTATED REFLECTIVE BOLLARD BOLLARD WITH REFERENCE
- REINSTATED TRAFFIC SIGN WITH REFERENCE
- BLISTER TACTILE PAVING. CONSTRUCTED TO HCC STANDARD HCC11/C/060 'UNCONTROLLED PEDESTRIAN CROSSING IN NEW WORKS'
- KERB INSTALLED IN ACCORDANCE WITH HCC11/C/010
- YELLOW COLOURED THERMOPLASTIC ROAD MARKING TO TSRGD DIAGRAM 1018.1, 75mm THICK
- 3m LENGTH OF FENCE TO BE REINSTATED AFTER DRAINAGE WORKS

© CROWN COPYRIGHT AND DATABASE RIGHTS 2026
ORDNANCE SURVEY 100019180

S3	P01	FIRST ISSUE	24.04.2026	YO	DJR	TS	JD
SUIT	REV	WORK IN PROGRESS ISSUE AND DESCRIPTION OF AMENDMENTS	DATE	DESIGNER	CAD	CHKD	APPD

CLIENT
**HAMPSHIRE COUNTY COUNCIL
UNIVERSAL SERVICES DIRECTORATE
TRANSPORT IMPLEMENTATION**

CONSULTANT

**Hampshire
County Council**
Engineering Services
TIM LAWTON BEng CEng FICE FCIHT - ASSISTANT DIRECTOR OF UNIVERSAL SERVICES

HORIZONTAL SCALE @ A1 1:200	SCHEME FIVE LANES, FOUR MARKS FLOOD ALLEVIATION	DRAWING TITLE GENERAL ARRANGEMENT
VERTICAL SCALE @ A1 N/A		
SHEET NUMBER 1 OF 1		JOB No. RJ508601.01 HCC CAD PLOT: 234/2026 21 29 36

DRAWING TITLE GENERAL ARRANGEMENT	
HCC CAD PLOT: 234/2026 21 29 36	
SUIT S3	REV P01